

Westfield Street Reconstruction/ Penhurst Street Curb Replacement
Public Informational Meeting
Westfield St. (Brooks Ave – Chili Ave.)
Penhurst Street (Westfield St – Genesee Park Blvd.)

DATE: August 24, 2010
TIME: 6:30 p.m.
LOCATION: Lincoln Park School #44, 820 Chili Avenue

I. Introduction

Al Giglio, Managing Engineer/Street Design Division, City of Rochester, DES
Frank Bonn, Engineer II/Street Design Division, City of Rochester, DES
Kevin Quinn, Senior Pure Waters Technician, MCPW

II. Sewer Replacement, MCPW

- o Replacement of existing sewer and manholes as required.
- o Replacement of existing house laterals to back of curb as required.
- o Temporary restoration of pavement and lawn areas.

III. General Project Description, City Roadway Contract

- o Replacement of lead and galvanized water services where required (East Side).
- o Installation of cathodic protection systems on both watermains.
- o Catch basins replacement for improved drainage.
- o Excavation of and removal of existing roadway.
- o New granite curbing with underdrain system.
- o Placement of new gravel and the first two asphalt layers
- o Adjustment of Catch Basin and Manhole frames
- o Replacement of most sidewalks.
- o New driveway aprons.
- o Final pavement.
- o Restoration of grass areas affected by the construction.

IV. Maintenance of Traffic

- o Traffic will be maintained using flag-persons when necessary.
- o Some access disruptions during curb, sidewalk and driveway placement.
- o Existing parking regulations will remain after the project is complete.

V. Schedule

- | | |
|--------------------------|----------------|
| o Bid and Award | Winter 2010/11 |
| o Street Construction | Spring 2011 |
| o Substantial Completion | Fall 2011 |

VI. Questions and Comments

VII. Contacts

Frank Bonn, DES/Street Design Division – Design Phase,
City of Rochester 428-8257
bonnf@cityofrochester.gov

Kevin Quinn, DES/Division of Engineering
MCPW 753-7652