


PLAN



ELEVATION

NOTES:

1. IF DIMENSION "A" BETWEEN THE CENTERLINE OF THE WATER MAIN AND THE FACE OF CURB IS 6 FEET OR LESS, THE CURB VALVE IS NOT REQUIRED.
2. ALL NEW SERVICE PIPE, FITTINGS AND VALVES SHALL BE RESTRAINED.
3. NEW WATER SERVICE SHALL BE PRESSURE TESTED FROM TEE TO TEMPORARY CAP IN ACCORDANCE WITH SPECIFICATION S900-3.05
4. WHEN LENGTH OF NEW WATER SERVICE EXCEEDS 50 FEET, SERVICE SHALL BE DISINFECTED IN ACCORDANCE WITH SPECIFICATION S900-3.06.
5. ON PLASTIC SERVICES, WHEN CURB VALVE IS NOT REQUIRED, EXTEND TRACER WIRE TO DUCTILE IRON CONNECTION PIPE AND FITTINGS AND ATTACH WIRE TO PIPE OR FITTING WITH THERMITE WELD.

CITY OF ROCHESTER		
REPLACEMENT OF		
4 INCH AND LARGER		
WATER SERVICE ON		
NEW WATER MAIN		
ISSUED	3-23-11	NON-STANDARD DWG.NO.S900-11
REVISED		