



ELEVATION

NOTES:

1. ONE CONTINUOUS PIECE OF WATER SERVICE PIPE IS TO BE INSTALLED BETWEEN THE CORPORATION STOP AND CURB STOP AND BETWEEN THE CURB STOP AND METER PIT (IF REQUIRED) OR BUILDING WALL.
2. A METER PIT MAY BE REQUIRED WHEN THE WATER SERVICE LENGTH, AS MEASURED FROM THE STREET RIGHT-OF-WAY LINE TO THE BUILDING WALL, EXCEEDS 100 FEET. WHEN THE WATER SERVICE LENGTH EXCEEDS 100 FEET, THE WATER BUREAU WILL REVIEW EACH NEW WATER SERVICE PLAN TO DETERMINE IF THE METER SHOULD EITHER BE PLACED; INSIDE OF THE HEATED BUILDING, IN A METER PIT OUTSIDE OF THE BUILDING NEAR THE RIGHT-OF-WAY LINE OR IN A HEATED ABOVE GROUND ENCLOSURE NEAR THE RIGHT-OF-WAY LINE.
3. A BACKFLOW PREVENTION DEVICE IS REQUIRED ON ALL DOMESTIC WATER SERVICES 1½" AND LARGER AND MAY BE REQUIRED ON SOME WATER SERVICES SMALLER THAN 1½", AS DETERMINED BY THE WATER BUREAU.

CITY OF ROCHESTER		
NEW WATER SERVICE 2 INCH AND SMALLER		
ISSUED	7-13-11	NON-STANDARD DWG.NO.S970-1
REVISED		