



CONCRETE CRADLE

STONE CRADLE

NOTES:

1. LIMITS SHOWN ARE MAXIMUM ALLOWED AND MINIMUM REQUIRED FOR EXCAVATION AND BACKFILL.
2. UPPER PAY LIMITS FOR TRENCH EXCAVATION IS TOP OF EXISTING SURFACE, AT TIME OF TRENCH EXCAVATION.
3. UPPER PAY LIMITS FOR ROCK EXCAVATION IS TOP SURFACE OF ROCK.
4. UPPER PAY LIMIT FOR SELECT GRANULAR BACKFILL (SEWER) IS BOTTOM OF TEMPORARY PAVEMENT (IF USED), OR FINISHED SURFACE IF SELECT GRANULAR BACKFILL (SEWER) IS PLACED UP TO FINISHED SURFACE AS NOTED ON THE DRAWINGS.
5. TEMPORARY OR PERMANENT BLOCKS OR ANY OTHER TYPE OF PIPE SUPPORT IS NOT TO BE USED DURING PIPE INSTALLATION.

CITY OF ROCHESTER	
SEWER LATERAL TRENCH RECONSTRUCTION AREA	
ISSUED 9-2-91	STD. DWG.
REVISED 10-21-03	NO. R601-1