

NOTES:

SECTION A-A

- 1. CAPSTONE TO BE REMOVED, CLEANED AND RETURNED TO MCPW.
- 2. REPAIR EXISTING WALLS CONSISTENT WITH ORIGINAL CONSTRUCTION.
- 3. USE CONCRETE OR BRICK AND MORTAR TO ADJUST TOP OF WALLS TO SET FRAME AND GRATE TO FINISHED GRADE AND ON SOUND BEARING.
- 4. COAT INTERIOR AREA OF NEW CONCRETE CONSTRUCTION WITH 2 COATS OF TAMMS DURALKOTE 240, OR APPROVED EQUIVALENT.
- 5. COAT EXPOSED EXTERIOR AREA OF NEW CONCRETE CONSTRUCTION WITH 2 COATS OF HI-BUILD BITUMINOUS COATING 35-J-10, KOPPERS BITMASTIC SUPER SERVICE BLACK, OR APPROVED EQUIVALENT.

CITY OF ROCHESTER

MODIFY EXISTING **CAPSTONE** CATCH BASIN

ISSUED 9-2-91 **STD. DWG.** REVISED₁₂₋₃₁₋₀₇ NO. R604-3